

**Alabama Department of Transportation  
Proposal Item Summary**

---

**025. STPAA-0207(502)**

**LAUDERDALE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-207 from the intersection of SR-2 (US-72) in Rogersville to a point 0.160 mile north of the junction of CR-55. Length 1.604 mi.

The Bracket Estimate on this project is from \$534,233 to \$652,952.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	3,001	Gal	Tack Coat
408B001	30,010	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	2,875	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	2	Mile	Scoring Bituminous Pavement Surface
430B042	214	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
641S500	10	Each	Valve Box Reset
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,000.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	13	Mile	Solid Temporary Traffic Stripe
703A002	1,582	SQFT	Traffic Control Markings, Class 2, Type A
703D001	748	SQFT	Temporary Traffic Control Markings
705A032	160	Each	Pavement Markers, Class A-H, Type 1-B
705A037	140	Each	Pavement Markers, Class A-H, Type 2-D
705A038	60	Each	Pavement Markers, Class A-H, Type 2-E
740B000	716	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car