

**Alabama Department of Transportation  
Proposal Item Summary**

**026. STPAA-0257(501)**

**WALKER COUNTY**

Contract Time: 70 Working Days

DBE Goal Percent: 1.00

for constructing the Widening, Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-257 from the junction of SR-195 to the junction of CR-43 northeast of Jasper. Length 6.739 mi.

The Bracket Estimate on this project is from \$2,898,046 to \$3,542,056.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	676	SQYD	Removing Concrete Driveway
305B077	2,069	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	25,725	Gal	Tack Coat
408B001	126,983	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	6,827	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	219	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	8,670	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B657	52	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	34	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	348	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	3,287	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	177	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	14	Mile	Scoring Bituminous Pavement Surface
433A000	120,915	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665Q002	100	LF	Wattle
674A000	525	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 155,000.00)
701A227	14	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,416	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	42	Mile	Solid Temporary Traffic Stripe
701G146	660	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	660	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,320	LF	Solid Traffic Stripe Removed (Tape)
703A002	6,683	SQFT	Traffic Control Markings, Class 2, Type A
703B002	443	SQFT	Traffic Control Legends, Class 2, Type A
703D001	644	SQFT	Temporary Traffic Control Markings

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A030	170	Each	Pavement Markers, Class A-H, Type 2-C
705A032	920	Each	Pavement Markers, Class A-H, Type 1-B
705A037	380	Each	Pavement Markers, Class A-H, Type 2-D
705A038	383	Each	Pavement Markers, Class A-H, Type 2-E
730H001	4,654	LF	Loop Wire
730I001	100	LF	Loop Detector Lead-In-Cable
730J010	1	Each	Vehicle Loop Detector
740B000	1,795	SQFT	Construction Signs
740C000	18	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2