

**Alabama Department of Transportation
Proposal Item Summary**

010. IM-I010(349)

MOBILE COUNTY

Contract Time: 120 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on I-10 from a point 1.360 miles east of the SR-193 Interchange (MP 18.467) to the Wallace Tunnel (MP 26.651) in Mobile. Length 8.272 mi.

The Bracket Estimate on this project is from \$5,832,333 to \$7,128,407.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	2,357	Gal	Tack Coat
408B001	486,705	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	20,870	Ton	Polymer Modified Open Graded Friction Course
420B000	83,479	Gal	Open Graded Friction Course Tack Coat
424A283	1,591	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	176,393	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
652C000	420	Acre	Mowing
665G000	50	Each	Sand Bags
665J002	2,000	LF	Silt Fence
665O001	2,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 312,700.00)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	16	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	42	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	853	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B063	11,690	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	7,033	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	125	Mile	Broken Temporary Traffic Stripe
701C001	94	Mile	Solid Temporary Traffic Stripe
701G142	12,998	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	4,059	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	4,059	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	1,605	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H002	8,118	LF	Solid Traffic Stripe Removed (Tape)
701H007	12,998	LF	Broken Traffic Stripe Removed (Tape)
701H012	853	LF	Dotted Traffic Stripe Removed (Tape)
703A002	36,132	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,744	SQFT	Traffic Control Legends, Class 2, Type A
703D001	25,902	SQFT	Temporary Traffic Control Markings
703H000	4,864	SQFT	Specialty Traffic Control Markings
705A022	1,000	Each	Pavement Markers, Class C, Type 2-C
705A030	13,946	Each	Pavement Markers, Class A-H, Type 2-C
705A031	200	Each	Pavement Markers, Class A-H, Type 1-A
705A032	2,730	Each	Pavement Markers, Class A-H, Type 1-B
728A000	2	Each	Truck Mounted Impact Attenuator Unit

Item No.	Quantity	Units	Description
740B000	2,239	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740D000	200	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	3	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2