

**Alabama Department of Transportation
Proposal Item Summary**

022. STPAA-0110(506)

MONTGOMERY COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-110 from a point 0.370 mile west of the junction of SR-293 southeast of Montgomery to the Bullock County Line. Length 6.423 mi.

The Bracket Estimate on this project is from \$2,163,297 to \$2,644,030.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B100	110,748	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	12,492	Gal	Tack Coat
408A052	118,974	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	9,461	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	354	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	839	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
652C000	55	Acre	Mowing
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 110,000.00)
701A227	14	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,866	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	43	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	428	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	214	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	8,854	SQFT	Traffic Control Markings, Class 2, Type A
703B002	471	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,639	SQFT	Temporary Traffic Control Markings
703E001	315	SQFT	Temporary Traffic Control Legends
705A030	287	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,044	Each	Pavement Markers, Class A-H, Type 1-B
705A037	438	Each	Pavement Markers, Class A-H, Type 2-D
705A038	754	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,497	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	