

**Alabama Department of Transportation  
Proposal Item Summary**

**023. STPAA-0168(502)**

**MARSHALL COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-168 from the intersection of Church Street in Boaz to the DeKalb County Line. Length 4.073 mi.

The Bracket Estimate on this project is from \$1,405,025 to \$1,717,253.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
209A000	1	Each	Mailbox Reset, Single
209A001	1	Each	Mailbox Reset, Double
405A000	6,720	Gal	Tack Coat
408B001	80,995	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	6,684	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	495	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
430B043	4,485	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	200	SQYD	Filter Blanket, Geotextile
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	400	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	31	Mile	Solid Temporary Traffic Stripe
701G251	3,000	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	2,645	SQFT	Traffic Control Markings, Class 2, Type A
703B002	183	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,264	SQFT	Temporary Traffic Control Markings
705A030	27	Each	Pavement Markers, Class A-H, Type 2-C
705A032	164	Each	Pavement Markers, Class A-H, Type 1-B
705A037	441	Each	Pavement Markers, Class A-H, Type 2-D
705A038	10	Each	Pavement Markers, Class A-H, Type 2-E
710A115	27	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710A157	8	SQFT	Class 9, Aluminum Flat Sign Panels 0.125" Thick (Type XI Background, Fluorescent)
710B001	48	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
740B000	2,328	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
7400000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit