

**Alabama Department of Transportation
Proposal Item Summary**

024. STPAA-0279(502)

JACKSON COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-279 from the junction of SR-79 to the junction of South Scott Street in Scottsboro. Length 3.179 mi.

The Bracket Estimate on this project is from \$1,983,820 to \$2,424,668.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	34	SQYD	Removing Concrete Sidewalk
206D001	950	LF	Removing Guardrail
206E008	7	Each	Removing Guardrail End Anchor (All Type)
405A000	10,277	Gal	Tack Coat
408B001	123,642	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	8,347	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	325	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	2,500	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	1,647	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
629E015	328	LF	Bridge Rail Retrofit, Type SC(CB)
630A001	963	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	3	Each	Guardrail End Anchor, Type 20 Series (MASH)
665Q002	600	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 107,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,835	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13	Mile	Broken Temporary Traffic Stripe
701C001	13	Mile	Solid Temporary Traffic Stripe
701G142	328	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	328	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	328	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	328	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	656	LF	Solid Traffic Stripe Removed (Tape)
701H007	656	LF	Broken Traffic Stripe Removed (Tape)
703A002	4,962	SQFT	Traffic Control Markings, Class 2, Type A
703B002	247	SQFT	Traffic Control Legends, Class 2, Type A
703D001	504	SQFT	Temporary Traffic Control Markings
705A030	542	Each	Pavement Markers, Class A-H, Type 2-C
705A032	95	Each	Pavement Markers, Class A-H, Type 1-B
705A037	832	Each	Pavement Markers, Class A-H, Type 2-D
705A038	48	Each	Pavement Markers, Class A-H, Type 2-E

Item No.	Quantity	Units	Description
730H001	2,000	LF	Loop Wire
740B000	1,391	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit