

**Alabama Department of Transportation
Proposal Item Summary**

031. STPSU-2815(252)

ETOWAH COUNTY

Contract Time: 100 Working Days

DBE Goal Percent: 3.00

for constructing the Roadway Improvements (Reconstruction) on South 11th Street from the junction of Black Creek Parkway to a point at Black Creek. Length 0.514 mi.

The Bracket Estimate on this project is from \$1,361,706 to \$1,664,307.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$21.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 2 Acres)
206C000	3	SQYD	Removing Concrete Sidewalk
206C010	150	SQYD	Removing Concrete Driveway
206C021	2	SQYD	Removing Concrete Steps
206D000	72	LF	Removing Pipe
206D003	2,153	LF	Removing Curb And Gutter
206E001	2	Each	Removing Inlets
206E042	1	Each	Removing Inlets (Partial)
209A000	5	Each	Mailbox Reset, Single
209A001	1	Each	Mailbox Reset, Double
210A000	3,934	CUYD	Unclassified Excavation
210D001	200	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	700	CUYD	Structure Excavation
214B001	289	CUYD	Foundation Backfill, Commercial
243A034	3,633	SQYD	Geosynthetic Reinforcement For Soft Soil Stabilization, Type 2
301A012	6,540	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
305B078	10	Ton	Crushed Aggregate, Section 825, Type B, For Miscellaneous Use
405A000	328	Gal	Tack Coat
408B001	2,773	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	675	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	858	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B013	1,771	Ton	Aggregate Surfacing (ALDOT #67)
430B035	22	Ton	Aggregate Surfacing (ALDOT #467, #410 Modified Or #57)
530A001	155	LF	18" Roadway Pipe (Class 3 R.C.)
530A033	33	LF	12" Roadway Pipe (Class 3 R.C.)
530B002	126	LF	29" Span, 18" Rise Roadway Pipe (Class 3 R.C.)
533A098	675	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A099	72	LF	24" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
602A000	24	Each	Right Of Way Markers
608A000	3,633	SQYD	Separation Geotextile
610D003	301	SQYD	Filter Blanket, Geotextile
618A000	2,098	SQYD	Concrete Sidewalk, 4" Thick
618B003	57	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
618C001	152	SQFT	Detectable Warning Surface

Item No.	Quantity	Units	Description
618D000	70	SQYD	Curb Ramp
621A005	2	Each	Junction Boxes, Type 1
621C001	1	Each	Inlets, Type B
621C015	10	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	4	Each	Inlets, Type S1 Or S3 (2 Wing)
621C036	1	Each	Inlets, Type S1 Or S3 (1 Wing) (Modified)
621C049	1	Each	Inlets, Type S1 Or S3 (2 Wing) (Modified)
621D015	1	Each	Inlet Units, Type S1 Or S3
623A000	522	LF	Concrete Gutter
623B000	103	LF	Concrete Curb, Type N
623C000	2,027	LF	Combination Curb & Gutter, Type C
650A000	318	CUYD	Topsoil
652A100	1	Acre	Seeding
654A000	618	SQYD	Solid Sodding
656A010	1	Acre	Mulching
665A000	2	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665E000	16	SQYD	Polyethylene
665G000	250	Each	Sand Bags
665J002	1,453	LF	Silt Fence
665N000	100	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	1,453	LF	Silt Fence Removal
665P005	22	Each	Inlet Protection, Stage 3 Or 4
665Q002	452	LF	Wattle
674A000	600	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 71,000.00)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	133	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	3	Mile	Solid Temporary Traffic Stripe
701E010	768	LF	Broken Temporary Traffic Stripe
701G256	384	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	455	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	910	SQFT	Temporary Traffic Control Markings
705A030	5	Each	Pavement Markers, Class A-H, Type 2-C
705A032	92	Each	Pavement Markers, Class A-H, Type 1-B
705A037	74	Each	Pavement Markers, Class A-H, Type 2-D
705A038	46	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,385	SQFT	Construction Signs
740D000	70	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	16	Each	Barricades, Type III
740G000	16	Each	Barricades, Type I, (Portable, 24 Inches Wide)
740I002	2	Each	Warning Lights, Type B
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	3	Each	Portable Changeable Message Sign, Type 2