

**Alabama Department of Transportation
Proposal Item Summary**

001. BR-0014(550)

ELMORE AND TALLAPOOSA COUNTIES

Contract Time: 230 Working Days

for constructing the Bridge Rehabilitation and Bridge Painting on SR-14 over the Tallapoosa River in Tallassee. Length 0.329 mi.

The Bracket Estimate on this project is from \$4,620,367 to \$5,647,116.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$23.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C012	64	SQYD	Removing Bridge Deck (Partial Only)
206D006	1,100	LF	Removing Industrial Fence
206D016	44	LF	Removing Existing Bridge Handrail
210A000	39	CUYD	Unclassified Excavation
260A000	5	CUYD	Cement Mortar Flowable Backfill, Mix 1
305A052	34	CUYD	Selected Materials, Section 820, Local Sand, For Miscellaneous Use
490A000	4,970	SQYD	Blast Cleaning
490B003	4,970	SQYD	Bridge Deck Overlay
490D000	470	SQFT	Bridge Deck Spall Repair
520A100	1	LS	Repairs to Existing Bridge, Station 9+68.140
520A101	1	LS	Repairs to Existing Bridge, Station 11+79.590
520A102	1	LS	Repairs to Existing Bridge, Station 12+49.250
520A103	1	LS	Repairs to Existing Bridge, Station 14+29.710
520A104	1	LS	Repairs to Existing Bridge, Station 21+36.710
520C000	1	LS	Raising Portion Of Existing Bridge Station 9+68.140
521B000	1	LS	Coating Existing Bridge At Station 9+68.140
600A000	1	LS	Mobilization
610C001	72	Ton	Loose Riprap, Class 2
610D003	60	SQYD	Filter Blanket, Geotextile
634A008	1,100	LF	Industrial Fence, 12 Feet High
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 146,200.00)
701A089	1	Mile	Solid White, Class W, Type A Traffic Stripe
701A097	1	Mile	Solid Yellow, Class W, Type A Traffic Stripe
701C005	1	Mile	Solid Temporary Traffic Stripe (Tape)
701D007	2	Mile	Solid Traffic Stripe Removed (Paint)
701D009	1	Mile	Solid Traffic Stripe Removed (Tape)
705A037	25	Each	Pavement Markers, Class A-H, Type 2-D
728A000	1	Each	Truck Mounted Impact Attenuator Unit
740B000	382	SQFT	Construction Signs
740D000	40	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	4	Each	Barricades, Type III
740M001	50	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2