

**Alabama Department of Transportation
Proposal Item Summary**

008. IM-HSIP-I020(367)

CALHOUN AND TALLADEGA COUNTIES

Contract Time: 40 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, OGFC Safety Treatment, and Traffic Stripe on I-20 from the H. J. Bentley Jr. Parkway Overpass (MP 181.747) to the SR-21 Interchange (MP 185.904) in Oxford. Length 4.157 mi.

The Bracket Estimate on this project is from \$2,902,046 to \$3,546,945.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
405A000	962 Gal	Tack Coat
408B001	183,680 SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1 Each	Material Remixing Device
420A015	10,583 Ton	Polymer Modified Open Graded Friction Course
420B000	26,240 Gal	Open Graded Friction Course Tack Coat
424B285	529 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
432A000	117,060 SQYD	High Density Mineral Bond
600A000	1 LS	Mobilization
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 160,000.00)
701A227	9 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	17 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,630 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	33 Mile	Broken Temporary Traffic Stripe
701C001	33 Mile	Solid Temporary Traffic Stripe
701E003	2,830 LF	Solid Temporary Traffic Stripe (Tape)
701E013	5,661 LF	Broken Temporary Traffic Stripe (Tape)
701G142	2,831 LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,415 LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,415 LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	3,300 LF	Solid Traffic Stripe Removed (Tape)
703A002	2,680 SQFT	Traffic Control Markings, Class 2, Type A
703D001	500 SQFT	Temporary Traffic Control Markings
705A030	1,560 Each	Pavement Markers, Class A-H, Type 2-C
705A031	200 Each	Pavement Markers, Class A-H, Type 1-A
705A032	81 Each	Pavement Markers, Class A-H, Type 1-B
731B000	1 Each	Pole for Mounting Traffic Detection Equipment
740B000	2,572 SQFT	Construction Signs
740D000	600 Each	Channelizing Drums
741C010	2 Each	Portable Sequential Arrow And Chevron Sign Unit
742A003	2 Each	Portable Changeable Message Sign, Type 3