

**Alabama Department of Transportation
Proposal Item Summary**

012. IM-I565(319)

MADISON COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe of the Travel Lanes and Inside Shoulders on I-565 from the Limestone County Line to a point east of the bridge over Intergraph Way (MP 9.880) in Madison. Length 2.854 mi.

The Bracket Estimate on this project is from \$1,992,649 to \$2,435,460.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	9,548	Gal	Tack Coat
408A053	106,394	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
423A003	11,040	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
424B585	1,000	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
428A001	6	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
610D003	500	SQYD	Filter Blanket, Geotextile
665Q002	1,500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 106,800.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	8	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B059	309	LF	Dotted, Class W, Type A Traffic Stripe(Lane Drop 10" Wide)
701B063	8,034	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B075	309	LF	Dotted, Class W, Type B Traffic Stripe, Black (Lane Drop 10" Wide)
701B207	4,003	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
701G142	1,419	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,110	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,110	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	2,220	LF	Solid Traffic Stripe Removed (Tape)
701H007	1,728	LF	Broken Traffic Stripe Removed (Tape)
703A002	4,627	SQFT	Traffic Control Markings, Class 2, Type A
703B002	683	SQFT	Traffic Control Legends, Class 2, Type A
703B011	123	SQFT	Traffic Control Legends, Class W, Type A
705A030	820	Each	Pavement Markers, Class A-H, Type 2-C
705A031	873	Each	Pavement Markers, Class A-H, Type 1-A
705A032	189	Each	Pavement Markers, Class A-H, Type 1-B
705A037	360	Each	Pavement Markers, Class A-H, Type 2-D
731B000	1	Each	Pole for Mounting Traffic Detection Equipment
740B000	2,006	SQFT	Construction Signs
740C000	78	SQFT	Special Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone

Item No.	Quantity	Units	Description
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2