

**Alabama Department of Transportation
Proposal Item Summary**

021. STPMN-5117(254)

MONTGOMERY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Intersection Improvements on CR-626 (Vaughn Road) at Ryan Road in Montgomery. Length 0.198 mi.

The Bracket Estimate on this project is from \$373,496 to \$456,495.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$17.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206C010	16	SQYD	Removing Concrete Driveway
206E000	1	Each	Removing Headwalls
210A000	332	CUYD	Unclassified Excavation
210D021	250	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	4	CUYD	Structure Excavation
214B001	3	CUYD	Foundation Backfill, Commercial
230A000	11	RBST	Roadbed Processing
243A034	1,803	SQYD	Geosynthetic Reinforcement For Soft Soil Stabilization, Type 2
305B077	1,339	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A000	1,339	SQYD	Bituminous Treatment A
405A000	174	Gal	Tack Coat
408B001	3,975	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	410	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	111	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B691	115	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
530A100	10	LF	15" Roadway Pipe (Class 3 R.C.) (Extension)
600A000	1	LS	Mobilization
610D003	370	SQYD	Filter Blanket, Geotextile
619A001	1	Each	15" Roadway Pipe End Treatment, Class 1
650A000	220	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665F000	50	Each	Hay Bales
665G000	50	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665N000	25	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	1,000	LF	Silt Fence Removal
665Q002	392	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	210	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	3	Mile	Solid Temporary Traffic Stripe
703A002	702	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A
703D001	702	SQFT	Temporary Traffic Control Markings
705A030	10	Each	Pavement Markers, Class A-H, Type 2-C
705A032	261	Each	Pavement Markers, Class A-H, Type 1-B
705A037	5	Each	Pavement Markers, Class A-H, Type 2-D
705A038	130	Each	Pavement Markers, Class A-H, Type 2-E
740B000	356	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
745A000	480	HOUR	Uniformed Police Officer