

**Alabama Department of Transportation
Proposal Item Summary**

027. STPSU-I085(370)

LEE COUNTY

Contract Time: 140 Working Days

DBE Goal Percent: 1.00

for constructing the Interchange Lighting and Landscaping on I-85 at the Bent Creek Road Interchange (Exit 57) in Auburn. Length 0.833 mi.

The Bracket Estimate on this project is from \$1,545,421 to \$1,888,848.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$17.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
600A000	1	LS	Mobilization
654A000	600	SQYD	Solid Sodding
660A000	225	CUYD	Plant Topsoil
660C060	527	Each	Shrubs, Juniperus Chinensis 'Pfitzeriana Compacta' (Nick's Compact Juniper)
660C073	497	Each	Shrubs, Loropetalum Chinense (Loropetalum)
660C084	28	Each	Shrubs, Myrica Pusilla (Dwarf Wax Myrtle)
660D011	42	Each	Trees, Chionanthus Virginicus (Fringe Tree)
660D012	15	Each	Trees, Betula Nigra 'BNMTF' ('Dura Heat' River Birch)
660D042	30	Each	Trees, Lagerstroemia Indica 'Tuscarora' (Tuscarora Crepe Myrtle)
660D049	18	Each	Trees, Liriodendron Tulipifera (Tulip Popular)
660D072	19	Each	Trees, Nyssa Sylvatica 'Wildfire' ('Wildfire' Blackgum)
660D109	21	Each	Trees, Taxodium Ascendens (Pond Cypress)
660D124	32	Each	Trees, Quercus Virginiana 'Cathedral' (Cathedral Live Oak)
660D165	50	Each	Trees, Magnolia Virginiana 'Jim Wilson' ('Moon Glow' Sweet Bay Magnolia)
660D166	24	Each	Trees, Magnolia Grandiflora (Southern Charm)
660D180	28	Each	Trees, Magnolia Grandiflora 'Little Gem' (Little Gem Magnolia)
660J000	470	CUYD	Plant Mulch
665B001	3	Ton	Temporary Mulching
665G000	450	Each	Sand Bags
665J002	800	LF	Silt Fence
665O001	800	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 82,300.00)
728A000	1	Each	Truck Mounted Impact Attenuator Unit
740B000	1,349	SQFT	Construction Signs
740C000	18	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750A261	7	Each	High Mast Luminaire Assembly with Three, LED, 400 Watt Equivalent Luminaires
750A262	5	Each	High Mast Luminaire Assembly with Four, LED, 400 Watt Equivalent Luminaires
750A263	1	Each	High Mast Luminaire Assembly with Five, LED, 400 Watt Equivalent Luminaires
750B581	4	Each	Roadway Luminaire Assembly with One, LED Low Profile Underpass Surface Mount, 150 Watt Equivalent Luminaire
750B662	17	Each	Roadway Luminaire Assembly with One, Decorative LED, 400 Watt Equivalent Luminaire
750C010	17	Each	Pole Foundation,Roadway
750C011	13	Each	Pole Foundation, High Mast

Item No.	Quantity	Units	Description
750D200	12	Each	Electrical Junction Box, Type 1
750E123	550	LF	Conduit, 3/4 Inch, Rigid Metallic
750E127	50	LF	Conduit, 2 Inch, Rigid Metallic
750F022	500	LF	Conductor, #10 AWG
750F026	150	LF	Conductor, #2 AWG
750G010	10,000	LF	Combined Duct And Cable, 2 #6 AWG/ 1 #6 AWG GND
750G030	3,500	LF	Combined Duct and Cable, 2 #2 AWG/ 1 #6 AWG GND
750H005	1	Each	Service Pole
750I015	1	Each	Lighting Control Center
751K000	8	Each	Replace Roadway Luminaire (Including All Mounting Appurtenances)
751L022	8	Each	Remove Roadway Luminaire
756A028	910	LF	6" Electrical Conduit, 1 Line, Type 5 Installation