

**Alabama Department of Transportation  
Proposal Item Summary**

**014. IM-1065(527)**

**LIMESTONE COUNTY**

Contract Time: February 16, 2024 Completion Date

DBE Goal Percent: 4.00

for constructing the Welcome Center Replacement (Site Construction/Grading, Drainage, Pavement, Lighting, and Structures) on I-65 north of Athens. Length 0.839 mi.

The Bracket Estimate on this project is from \$5,539,712 to \$6,770,759.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$56.00 per set.

*The Principal Items of work are approximately as follows:*

**A MANDATORY pre-bid conference is scheduled for 1:30 p.m. on Thursday, August 11, 2022, at the Alabama Department of Transportation, North Region Office; 1525 Perimeter Parkway; Suite 400; Huntsville, AL 35806 Any qualified bidder wishing to bid this proposal is required to have a company representative present at this MANDATORY pre-bid conference. Proposals issued to bidders who fail to attend the MANDATORY pre-bid conference and/or register their attendance will be voided and their bids will not be received nor considered.**

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 12 Acres)
205A001	1	Each	Removal Of Structures, Structure No. 1
205A002	9	Each	Removal Of Structures, Structure No. 2
205A003	4	Each	Removal Of Structures, Structure No. 3
205A004	5	Each	Removal Of Structures, Structure No. 4
206C000	2,578	SQYD	Removing Concrete Sidewalk
206C002	140	SQYD	Removing Concrete Slope Paving
206C003	307	SQYD	Removing Concrete Flumes
206D000	1,668	LF	Removing Pipe
206D003	3,609	LF	Removing Curb And Gutter
206D011	140	LF	Removing Fence
206E001	14	Each	Removing Inlets
206E035	11	Each	Removing Concrete Picnic Tables
210A000	14,410	CUYD	Unclassified Excavation
210D000	1,500	CUYD	Borrow Excavation
214A000	3,309	CUYD	Structure Excavation
214B001	605	CUYD	Foundation Backfill, Commercial
230A000	32	RBST	Roadbed Processing
301A012	15,343	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
305B079	255	Ton	Crushed Aggregate, Section 825, Type A, For Miscellaneous Use
401A000	15,343	SQYD	Bituminous Treatment A
405A000	4,196	Gal	Tack Coat
408B001	14,173	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	2,404	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	390	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B651	1,630	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	30	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	2,388	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C360	104	Ton	Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B003	114	Ton	Aggregate Surfacing (ALDOT #57)
430B040	118	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)

Item No.	Quantity	Units	Description
430B050	524	Ton	Aggregate Surfacing(ALDOT#1)
502A000	344	LB	Steel Reinforcement
530A001	692	LF	18" Roadway Pipe (Class 3 R.C.)
530A002	358	LF	24" Roadway Pipe (Class 3 R.C.)
530A003	368	LF	30" Roadway Pipe (Class 3 R.C.)
530A004	318	LF	36" Roadway Pipe (Class 3 R.C.)
533A100	250	LF	30" Storm Sewer Pipe (Class 3 R.C.)
533A903	107	LF	8" Storm Sewer Pipe (Polyethylene)
535A239	17	LF	6" Side Drain Pipe (PVC)
535A240	17	LF	12" Side Drain Pipe (PVC)
600A000	1	LS	Mobilization
610C000	1	Ton	Loose Riprap, Class 1
610D003	231	SQYD	Filter Blanket, Geotextile
614A000	45	CUYD	Slope Paving
618A000	2,912	SQYD	Concrete Sidewalk, 4" Thick
618C001	240	SQFT	Detectable Warning Surface
618D000	184	SQYD	Curb Ramp
620A000	81	CUYD	Minor Structure Concrete
621A019	2	Each	Junction Boxes, Type 1 Or 2P
621B014	3	Each	Junction Box Units, Type 1 Or 2P
621C015	1	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	8	Each	Inlets, Type S1 Or S3 (2 Wing)
621C018	2	Each	Inlets, Type S2 Or S4 (2 Wing)
621C021	1	Each	Inlets, Type P2 Or P3
621C109	1	Each	Inlets, Type PD
621D015	9	Each	Inlet Units, Type S1 Or S3
621D016	1	Each	Inlet Units, Type S2 Or S4
621E004	2	Each	Manholes, Type L Or M (Storm)
623A001	97	LF	Concrete Gutter (Valley)
623C000	4,240	LF	Combination Curb & Gutter, Type C
630A001	650	LF	Steel Beam Guardrail, Class A, Type 2
630C029	1	Each	Guardrail End Anchor, Type 13 (Temporary)
630C077	1	Each	Guardrail End Anchor, Type 8 (MASH)
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
632A001	650	LF	Headlight Glare Screen (Mounted On Guardrail Posts)
634A002	338	LF	Industrial Fence, 6 Feet High
640B005	1	LS	Underground Utility Adjustment (Water)
640B006	1	LS	Underground Utility Adjustment (Sewerage)
650A000	108	CUYD	Topsoil
650B000	2,520	CUYD	Topsoil From Stockpiles
654A006	15,599	SQYD	Solid Sodding (Myers Zoysia)
665A000	4	Acre	Temporary Seeding
665B001	29	Ton	Temporary Mulching
665E000	1,800	SQYD	Polyethylene
665G000	60	Each	Sand Bags
665J002	2,400	LF	Silt Fence
665N000	172	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	2,400	LF	Silt Fence Removal
665P005	34	Each	Inlet Protection, Stage 3 Or 4
665Q002	200	LF	Wattle
674A000	500	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 223,320.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701B207	300	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C004	1	Mile	Broken Temporary Traffic Stripe (Tape)
701C005	1	Mile	Solid Temporary Traffic Stripe (Tape)
701D009	1	Mile	Solid Traffic Stripe Removed (Tape)
701D016	1	Mile	Broken Traffic Stripe Removed (Tape)
703A002	2,357	SQFT	Traffic Control Markings, Class 2, Type A
703B002	41	SQFT	Traffic Control Legends, Class 2, Type A
703H000	24	SQFT	Specialty Traffic Control Markings
705A000	180	Each	Pavement Markers, Class A, Type 1-A
705A004	29	Each	Pavement Markers, Class A, Type 2-C
705A011	228	Each	Pavement Markers, Class C, Type 1-A
705A022	29	Each	Pavement Markers, Class C, Type 2-C
710A160	126	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A170	5	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	280	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
726A000	1,480	LF	Portable Concrete Safety Barriers, Type 6
740B000	771	SQFT	Construction Signs
740C000	76	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
740E000	40	Each	Cones (36 Inches High)
740M001	40	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750A262	4	Each	High Mast Luminaire Assembly with Four, LED, 400 Watt Equivalent Luminaires
750B601	26	Each	Roadway Luminaire Assembly with One, LED, 250 Watt Equivalent Luminaire
750B602	16	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750C010	26	Each	Pole Foundation, Roadway
750C011	4	Each	Pole Foundation, High Mast
750D200	10	Each	Electrical Junction Box, Type 1
750E114	50	LF	Conduit, 1 1/2 Inch, Rigid Nonmetallic
750F024	50	LF	Conductor, #6 AWG
750F027	100	LF	Conductor, #1/0 AWG
750G010	6,000	LF	Combined Duct And Cable, 2 #6 AWG/ 1 #6 AWG GND
750G030	1,500	LF	Combined Duct and Cable, 2 #2 AWG/ 1 #6 AWG GND
750H005	1	Each	Service Pole
750I015	1	Each	Lighting Control Center
751J006	40	Each	Remove Luminaire Pole Foundation, Concrete
751L002	1	Each	Remove Lighting Control Center, 6 Circuit
751L015	1	Each	Remove Service Pole
751L025	40	Each	Remove Roadway Luminaire Assembly
751M000	1	LS	Remove Conductors
756A028	255	LF	6" Electrical Conduit, 1 Line, Type 5 Installation
770V003	1	LS	Maintenance Building
771G000	1	LS	Generator and Foundation
791D000	4	Each	Outdoor Shelters
792A000	4	Each	Site Furnishings ( Park Bench)
792A001	16	Each	Site Furnishings ( Picnic Table)
792A002	17	Each	Site Furnishings ( Trash Receptacle)