

**Alabama Department of Transportation  
Proposal Item Summary**

**018. NH-0009(584)**

**COVINGTON COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 2.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-9 (US-331) from the junction of CR-38 in Opp to the Crenshaw County Line. Length 7.885 mi.

The Bracket Estimate on this project is from \$2,100,751 to \$2,567,585.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	19,890	Gal	Tack Coat
408A052	132,599	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	14,595	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	50	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	17	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	1,974	CUYD	Topsoil
652A100	8	Acre	Seeding
652C000	50	Acre	Mowing
656A010	8	Acre	Mulching
665A000	23	Acre	Temporary Seeding
665B001	69	Ton	Temporary Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
666A001	8	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 112,300.00)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20	Mile	Broken Temporary Traffic Stripe
701C001	44	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	634	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,268	SQFT	Temporary Traffic Control Markings
705A032	266	Each	Pavement Markers, Class A-H, Type 1-B
705A037	373	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,416	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	