

**Alabama Department of Transportation
Proposal Item Summary**

024. STPMN-2620(258)

ELMORE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on Cobbs Ford Road/Alabama River Parkway from the junction of South Edgewood Road East in Millbrook to the junction of Jackson Lake Road. Length 2.827 mi.

The Bracket Estimate on this project is from \$1,254,622 to \$1,533,427.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	1	Each	Removing Guardrail End Anchor (All Type)
405A000	11,000	Gal	Tack Coat
408A051	110,000	SQYD	Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
424A366	9,100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 66,800.00)
701A231	7	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	1,213	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	25	Mile	Broken Temporary Traffic Stripe
701C001	30	Mile	Solid Temporary Traffic Stripe
701G251	800	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	2,175	SQFT	Traffic Control Markings, Class 2, Type A
703B002	485	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,959	SQFT	Temporary Traffic Control Markings
705A030	68	Each	Pavement Markers, Class A-H, Type 2-C
705A031	345	Each	Pavement Markers, Class A-H, Type 1-A
705A032	128	Each	Pavement Markers, Class A-H, Type 1-B
705A037	469	Each	Pavement Markers, Class A-H, Type 2-D
705A038	64	Each	Pavement Markers, Class A-H, Type 2-E
740B000	466	SQFT	Construction Signs
740D000	75	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit