

**Alabama Department of Transportation
Proposal Item Summary**

040. RACR-017-000-010

FRANKLIN, LAWRENCE, AND COLBERT COUNTIES

Contract Time: 60 Working Days

for constructing the Intersection Improvements (Concrete Paving) on SR-2 (US-72) at Woodmont Drive in Tuscumbia (Site 1); on SR-33 at Court Street in Moulton (Site 2); and on SR-13 (US-43) at the Wal-Mart Entrance in Russellville (Site 3). Length 0.258 mi.

The Bracket Estimate on this project is from \$1,464,089 to \$1,789,442.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$18.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|---|
| 210A000 | 1,794 | CUYD | Unclassified Excavation |
| 327A021 | 1,042 | Ton | Plant Mix Bituminous Base, Mix 2 |
| 424B655 | 50 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 430B014 | 50 | Ton | Aggregate Surfacing (ALDOT #410 Modified) |
| 430B046 | 50 | Ton | Aggregate Surfacing (Aldot #2) |
| 450A007 | 402 | SQYD | Plain Cement Concrete Pavement,12 Inches Thick |
| 450A019 | 966 | SQYD | Plain Cement Concrete Pavement,10 Inches Thick |
| 450A025 | 2,800 | SQYD | Plain Cement Concrete Pavement,11 Inches Thick |
| 600A000 | 1 | LS | Mobilization |
| 680A001 | 1 | LS | Geometric Controls |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 75,500.00) |
| 701B027 | 439 | LF | Dotted, Class W, Type A Traffic Stripe (5" Wide) |
| 701E000 | 1,937 | LF | Solid Temporary Traffic Stripe |
| 701E006 | 1,190 | LF | Solid Temporary Traffic Stripe (Removable Tape) |
| 701E010 | 875 | LF | Broken Temporary Traffic Stripe |
| 701G141 | 898 | LF | Broken White, Class W, Type A Traffic Stripe (6" Wide) |
| 701G146 | 1,565 | LF | Solid White, Class W, Type A Traffic Stripe (5"Wide) |
| 701G154 | 1,297 | LF | Solid Yellow, Class W, Type A Traffic Stripe (5" Wide) |
| 701H000 | 677 | LF | Solid Traffic Stripe Removed (Paint) |
| 701H005 | 570 | LF | Broken Traffic Stripe Removed (Paint) |
| 703A011 | 463 | SQFT | Traffic Control Markings, Class W, Type A |
| 703B011 | 68 | SQFT | Traffic Control Legends, Class W, Type A |
| 703D001 | 124 | SQFT | Temporary Traffic Control Markings |
| 705A030 | 46 | Each | Pavement Markers, Class A-H, Type 2-C |
| 705A037 | 55 | Each | Pavement Markers, Class A-H, Type 2-D |
| 730H001 | 4,550 | LF | Loop Wire |
| 730I001 | 3,100 | LF | Loop Detector Lead-In-Cable |
| 730K000 | 7 | Each | Traffic Signal Junction Box |
| 730L005 | 3,100 | LF | 2", Non-Metallic, Conduit |
| 740B000 | 2,389 | SQFT | Construction Signs |
| 740D000 | 150 | Each | Channelizing Drums |
| 740E000 | 150 | Each | Cones (36 Inches High) |
| 740F002 | 20 | Each | Barricades, Type III |
| 740M001 | 150 | Each | Ballast For Cone |
| 741C010 | 2 | Each | Portable Sequential Arrow And Chevron Sign Unit |