

**Alabama Department of Transportation
Proposal Item Summary**

041. RACR-049-013-012

MOBILE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Intersection Improvements (Concrete Paving) on SR-13 (US-43) at Jackson Road in Satsuma. Length 0.147 mi.

The Bracket Estimate on this project is from \$752,699 to \$919,965.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206C002	70	SQYD	Removing Concrete Slope Paving
206D003	126	LF	Removing Curb And Gutter
206D006	100	LF	Removing Industrial Fence
210A000	1,471	CUYD	Unclassified Excavation
210D022	393	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))
301A012	1,492	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
405A000	33	Gal	Tack Coat
424A283	25	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424A369	36	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B040	115	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
450A019	1,452	SQYD	Plain Cement Concrete Pavement,10 Inches Thick
600A000	1	LS	Mobilization
614A000	14	CUYD	Slope Paving
623B000	69	LF	Concrete Curb, Type N
623B001	57	LF	Concrete Curb, Type N Special
634A002	100	LF	Industrial Fence, 6 Feet High
650A000	5	CUYD	Topsoil
650B000	33	CUYD	Topsoil From Stockpiles
654A001	48	SQYD	Solid Sodding (Bermuda)
665C010	118	LF	Temporary Pipe
665E000	1,500	SQYD	Polyethylene
665G000	50	Each	Sand Bags
665J002	360	LF	Silt Fence
665O001	360	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 43,000.00)
701G146	205	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	126	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A011	675	SQFT	Traffic Control Markings, Class W, Type A
703B011	23	SQFT	Traffic Control Legends, Class W, Type A
703D000	20	SQFT	Temporary Traffic Control Markings (Tape)
703D001	66	SQFT	Temporary Traffic Control Markings
705A030	99	Each	Pavement Markers, Class A-H, Type 2-C
705A037	2	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,069	SQFT	Construction Signs
740C000	21	SQFT	Special Construction Signs
740D000	150	Each	Channelizing Drums

Item No.	Quantity	Units	Description
740F002	6	Each	Barricades, Type III
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2