

**Alabama Department of Transportation
Proposal Item Summary**

042. RACR-066-010-004

WILCOX COUNTY

Contract Time: 60 Calendar Days

DBE Goal Percent: 1.00

for constructing the Intersection Improvements (Concrete Paving) on SR-10 at SR-28 in Camden. Length 0.151 mi.

The Bracket Estimate on this project is from \$1,481,577 to \$1,810,816.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D002	1,482	LF	Removing Curb
206D007	57	LF	Removing Concrete Flume
210A000	2,416	CUYD	Unclassified Excavation
210D021	75	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
301A012	5,798	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
450A004	5,230	SQYD	Plain Cement Concrete Pavement, 9 Inches Thick
600A000	1	LS	Mobilization
614A000	33	CUYD	Slope Paving
623B000	289	LF	Concrete Curb, Type N
623B001	155	LF	Concrete Curb, Type N Special
650A000	320	CUYD	Topsoil
654A000	1,437	SQYD	Solid Sodding
665Q002	300	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,200.00)
701G146	2,097	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	2,136	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A011	1,708	SQFT	Traffic Control Markings, Class W, Type A
703B011	96	SQFT	Traffic Control Legends, Class W, Type A
705A030	300	Each	Pavement Markers, Class A-H, Type 2-C
705A037	29	Each	Pavement Markers, Class A-H, Type 2-D
710B021	224	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
711A000	1	LS	Roadway Sign Relocation
740B000	1,470	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740F002	22	Each	Barricades, Type III
742A001	6	Each	Portable Changeable Message Sign, Type 2