

**Alabama Department of Transportation  
Proposal Item Summary**

---

**001. BR-0012(576)**

**HOUSTON COUNTY**

Contract Time: 200 Working Days

for constructing the Bridge Deck Repair (Hydroblasting and Deck Rehabilitation) on SR-12 (US-84) over the Chattahoochee River (MP 231.490 to MP 231.670) southwest of Gordon. Length 0.180 mi.

The Bracket Estimate on this project is from \$3,663,028 to \$4,477,034.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
521B000	1	LS	Coating Existing Bridge At Station 1260+49.06
544A000	3,928	SQYD	Hydroblasting
544B000	50	SQYD	Bridge Deck Repair with Formwork
544C000	3,928	SQYD	Placing and Finishing Concrete Overlay
544D000	174	CUYD	Concrete for Overlay
600A000	1	LS	Mobilization
665G000	50	Each	Sand Bags
665J002	250	LF	Silt Fence
665L000	250	LF	Floating Basin Boom
665O001	250	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 196,000.00)
701G142	955	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	955	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	955	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	955	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
705A030	12	Each	Pavement Markers, Class A-H, Type 2-C
726A000	1,206	LF	Portable Concrete Safety Barriers, Type 6
726D025	1	Each	Portable Impact Attenuator Assembly (Unidirectional, TL-3)
740B000	353	SQFT	Construction Signs
740D000	60	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	1	Each	Portable Changeable Message Sign, Type 2