

**Alabama Department of Transportation
Proposal Item Summary**

011. FBD-NR21(916)

MOBILE COUNTY

Contract Time: 50 Working Days

for constructing the Dock Repairs at the Mobile Ferry Dock (East Dock) in Dauphin Island.

The Bracket Estimate on this project is from \$539,970 to \$659,963.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	71	SQYD	Removing Concrete Driveway
210D024	10	CUYD	Borrow Excavation (A-3 Or Better) Loose Truckbed Measure
210E000	105	CUYD	Borrow Excavation (Underwater Backfill)
301A012	71	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	71	SQYD	Bituminous Treatment A
502A001	8,120	LB	Steel Reinforcement (Grade 60)
505E000	2,240	LF	Permanent Steel Sheet Piling
508A000	2,807	LB	Structural Steel
510B001	60	CUYD	Bridge Concrete, Class B
600A000	1	LS	Mobilization
610D003	12	SQYD	Filter Blanket, Geotextile
618B003	71	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
634A014	68	LF	Industrial Fence, 4 Feet High (P.V.C. Coated)
665E000	270	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665J002	100	LF	Silt Fence
665L000	167	LF	Floating Basin Boom
665O001	100	LF	Silt Fence Removal
674A000	138	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 29,000.00)
703A002	27	SQFT	Traffic Control Markings, Class 2, Type A
703A011	45	SQFT	Traffic Control Markings, Class W, Type A
705A039	35	Each	Pavement Markers, Class A-H, Type 2-A
707B014	2	Each	Type B Object Marker Installation
710A170	3	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	14	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	100	SQFT	Construction Signs
740D000	10	Each	Channelizing Drums
740F002	2	Each	Barricades, Type III