

**Alabama Department of Transportation  
Proposal Item Summary**

---

**031. STPMN-5121(250)**

**MONTGOMERY COUNTY**

Contract Time: 35 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-15 (Wadsen Road) from the Lowndes County Line to the junction of CR-15 (Lamar Road) southwest of Montgomery (Site 1) and on CR-15 (Lamar Road) from the junction of CR-15 (Wadsen Road) to the junction of SR-8 (US-80) in Montgomery (Site 2). Length 5.843 mi.

The Bracket Estimate on this project is from \$1,172,932 to \$1,433,583.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	9,396	Gal	Tack Coat
408A052	1,190	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A340	2,935	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A346	3,413	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B638	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	2,655	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,945	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 62,000.00)
701A231	12	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	11	Mile	Solid Temporary Traffic Stripe
703A002	336	SQFT	Traffic Control Markings, Class 2, Type A
703B002	69	SQFT	Traffic Control Legends, Class 2, Type A
705A032	171	Each	Pavement Markers, Class A-H, Type 1-B
705A037	581	Each	Pavement Markers, Class A-H, Type 2-D
740B000	676	SQFT	Construction Signs
740O000	1	Each	Pilot Car