

**Alabama Department of Transportation
Proposal Item Summary**

037. STPSU-0819(254)

CALHOUN COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for the constructing the Resurfacing and Traffic Stripe on Country Club Drive Southwest and Henry Road from the junction of Fairway Drive to the junction of SR-21 in Jacksonville. Length 0.822 mi.

The Bracket Estimate on this project is from \$691,876 to \$845,626.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$16.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	168	SQYD	Removing Concrete Driveway
206D000	120	LF	Removing Pipe
206D002	200	LF	Removing Curb
206E039	5	Each	Removing Mailboxes (Including Reset With a New 2 Inch Metal Or 4 Inch Timber Post)
210A000	715	CUYD	Unclassified Excavation
210D013	200	CUYD	Borrow Excavation (A-4(0) or Better)
212A000	60	STA	Machine Grading Shoulders
214A000	321	CUYD	Structure Excavation
214B001	78	CUYD	Foundation Backfill, Commercial
301A012	46	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A006	14,842	SQYD	Bituminous Treatment G
405A000	1,611	Gal	Tack Coat
424A340	1,115	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	325	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	75	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	160	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B676	66	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
530A002	72	LF	24" Roadway Pipe (Class 3 R.C.)
530B001	192	LF	22" Span, 14" Rise Roadway Pipe (Class 3 R.C.)
535A000	65	LF	15" Side Drain Pipe
535B088	120	LF	22" Span, 14" Rise Side Drain Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
618B003	182	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A003	1	Each	24" Roadway Pipe End Treatment, Class 1
619A100	3	Each	15" Side Drain Pipe End Treatment, Class 1
619B116	6	Each	22" Span, 14" Rise Side Drain Pipe End Treatment, Class 1
621C041	4	Each	Inlets, Type B (Modified)
623B000	315	LF	Concrete Curb, Type N
650A000	529	CUYD	Topsoil
654A000	5,000	SQYD	Solid Sodding
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665J002	5,000	LF	Silt Fence
665O001	5,000	LF	Silt Fence Removal
665Q002	400	LF	Wattle

Item No.	Quantity	Units	Description
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 36,246.00)
701B207	50	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701E000	18,550	LF	Solid Temporary Traffic Stripe
701F000	50	LF	Dotted Temporary Traffic Stripe
701G253	9,150	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G256	1,800	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701G265	9,400	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	1,043	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,043	SQFT	Temporary Traffic Control Markings
703H000	72	SQFT	Specialty Traffic Control Markings
705A030	16	Each	Pavement Markers, Class A-H, Type 2-C
705A032	42	Each	Pavement Markers, Class A-H, Type 1-B
705A037	80	Each	Pavement Markers, Class A-H, Type 2-D
705A038	60	Each	Pavement Markers, Class A-H, Type 2-E
740B000	793	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit