

**Alabama Department of Transportation  
Proposal Item Summary**

**045. ATRP2-47-2021-255**

**MARION COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 1.00

for constructing the Intersection and Drainage Improvements (Shoulder Widening, Micro-Milling, Resurfacing, and Traffic Stripe) on SR-253 at Old Hackleburg Road in Hackleburg. Length 0.146 mi.

The Bracket Estimate on this project is from \$380,359 to \$464,884.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C003	10	SQYD	Removing Concrete Flumes
206D000	130	LF	Removing Pipe
206E000	1	Each	Removing Headwalls
210A000	432	CUYD	Unclassified Excavation
210D021	624	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	533	CUYD	Structure Excavation
214B001	122	CUYD	Foundation Backfill, Commercial
305B077	32	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
327A020	62	Ton	Plant Mix Bituminous Base, Mix 1
401A000	268	SQYD	Bituminous Treatment A
405A000	7,589	Gal	Tack Coat
408B001	2,699	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A340	246	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	54	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B646	27	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	18	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	47	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B000	21	Ton	Aggregate Surfacing (ALDOT #467 Or #57)
530A001	13	LF	18" Roadway Pipe (Class 3 R.C.)
530A003	170	LF	30" Roadway Pipe (Class 3 R.C.)
530A101	8	LF	18" Roadway Pipe (Class 3 R.C.) (Extension)
533A098	110	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A099	144	LF	24" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610C000	20	Ton	Loose Riprap, Class 1
610D003	16	SQYD	Filter Blanket, Geotextile
619A103	1	Each	30" Side Drain Pipe End Treatment, Class 1
620A000	2	CUYD	Minor Structure Concrete
621A011	1	Each	Junction Boxes, Type 1 Or 1P
621C109	7	Each	Inlets, Type PD
623C000	60	LF	Combination Curb & Gutter, Type C
650A000	168	CUYD	Topsoil
650B000	353	CUYD	Topsoil From Stockpiles
654A000	1,093	SQYD	Solid Sodding
665G000	600	Each	Sand Bags

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
665J002	600	LF	Silt Fence
665O001	600	LF	Silt Fence Removal
665Q002	600	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 19,400.00)
701E000	4,470	LF	Solid Temporary Traffic Stripe
701G253	1,526	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	1,418	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	100	SQFT	Traffic Control Markings, Class 2, Type A
703D001	100	SQFT	Temporary Traffic Control Markings
740B000	420	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone