

**Alabama Department of Transportation
Proposal Item Summary**

051. RACR-041-014-001

LEE COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 1.00

for constructing the Roadway Improvements (Concrete Paving and Traffic Stripe) on SR-14 at the Quarry Entrance at approximately MP 210.290 northeast of Notasulga. Length 0.278 mi.

The Bracket Estimate on this project is from \$1,607,058 to \$1,964,182.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D003	92	LF	Removing Curb And Gutter
210A000	1,700	CUYD	Unclassified Excavation
210D021	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
305B077	1,350	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A000	5,050	SQYD	Bituminous Treatment A
450A007	5,050	SQYD	Plain Cement Concrete Pavement,12 Inches Thick
454A008	180	LF	Cleaning and Sealing Concrete Pavement, Type I, Joints (Longitudinal Joints)
600A000	1	LS	Mobilization
610D003	2,400	SQYD	Filter Blanket, Geotextile
623C000	92	LF	Combination Curb & Gutter, Type C
650A000	50	CUYD	Topsoil
654A001	450	SQYD	Solid Sodding (Bermuda)
665E000	500	SQYD	Polyethylene
665Q002	400	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 94,000.00)
701B027	650	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B207	300	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C005	1	Mile	Solid Temporary Traffic Stripe (Tape)
701D009	1	Mile	Solid Traffic Stripe Removed (Tape)
701G146	1,800	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	2,750	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G253	1,300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	1,300	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701H001	2,600	LF	Solid Traffic Stripe Removed (Plastic)
701H011	300	LF	Dotted Traffic Stripe Removed (Plastic)
703A002	540	SQFT	Traffic Control Markings, Class 2, Type A
703A011	1,785	SQFT	Traffic Control Markings, Class W, Type A
703B011	90	SQFT	Traffic Control Legends, Class W, Type A
703C001	540	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D000	96	SQFT	Temporary Traffic Control Markings (Tape)
705A013	260	Each	Pavement Markers, Class C, Type 2-A
705A023	260	Each	Pavement Markers, Class C, Type 2-D
705A030	30	Each	Pavement Markers, Class A-H, Type 2-C
705A032	400	Each	Pavement Markers, Class A-H, Type 1-B
705A037	15	Each	Pavement Markers, Class A-H, Type 2-D
705A038	200	Each	Pavement Markers, Class A-H, Type 2-E
710A160	8	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	14	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2 ", 14 Ga Square Tubular Steel)

Item No.	Quantity	Units	Description
726A000	825	LF	Portable Concrete Safety Barriers, Type 6
726D025	4	Each	Portable Impact Attenuator Assembly (Unidirectional,TL-3)
740B000	417	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740F002	8	Each	Barricades, Type III
740M001	100	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A003	4	Each	Portable Changeable Message Sign, Type 3
745A000	150	HOUR	Uniformed Police Officer
757A012	3	Each	Portable Traffic Signal, Type TR2