

**Alabama Department of Transportation
Proposal Item Summary**

004. CRPNU-NR13(934)

BLOUNT, ST., AND CLAIR COUNTIES

Contract Time: 150 Working Days

DBE Goal Percent: 3.00

for constructing the Curb and Ramp Installations on SR-4, SR-7, SR-23, SR-25, SR-53, SR-75, and SR-144 at various locations in the East Central Region (Birmingham Area) as indicated in the plans.

The Bracket Estimate on this project is from \$876,487 to \$1,071,262.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$19.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	1,185	SQYD	Removing Concrete Sidewalk
206D002	106	LF	Removing Curb
206D003	944	LF	Removing Curb And Gutter
206D005	5	LF	Removing Gutter
517D000	230	LF	Sidewalk Handrail
600A000	1	LS	Mobilization
618A000	2,576	SQYD	Concrete Sidewalk, 4" Thick
618B003	18	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
618C001	1,030	SQFT	Detectable Warning Surface
618D000	1,087	SQYD	Curb Ramp
623B002	5	LF	Concrete Curb, Type A
623C000	91	LF	Combination Curb & Gutter, Type C
650A000	8	CUYD	Topsoil
654A001	107	SQYD	Solid Sodding (Bermuda)
674A000	750	LF	Construction Safety Fence
703A002	5,486	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
703C000	300	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
710A160	36	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	78	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
711A000	1	LS	Roadway Sign Relocation
740B000	704	SQFT	Construction Signs
740D000	105	Each	Channelizing Drums
740E000	90	Each	Cones (36 Inches High)
740G000	4	Each	Barricades, Type I, (Portable, 24 Inches Wide)
740M001	90	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit