

**Alabama Department of Transportation
Proposal Item Summary**

010. CRSAMB-4921(251), CRSAMB-4921(252), CRSAMB-4921(253), CRSAMB-4921(254), CRSAMB-4921(255), CRSAMB-4921(256) & CRSAMB-4921(257)

MOBILE COUNTY

Contract Time: 100 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on various routes at various locations in the Southwest Region (Mobile Area) as indicated in the plans. Length 9.076 mi.

The Bracket Estimate on this project is from \$1,895,115 to \$2,316,252.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$19.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	294	SQYD	Removing Concrete Sidewalk
206D003	60	LF	Removing Curb And Gutter
212A000	55	STA	Machine Grading Shoulders
243A034	4,332	SQYD	Geosynthetic Reinforcement For Soft Soil Stabilization, Type 2
305B078	972	Ton	Crushed Aggregate, Section 825, Type B, For Miscellaneous Use
401A000	4,332	SQYD	Bituminous Treatment A
405A000	13,377	Gal	Tack Coat
408B000	25,304	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
424A336	4,936	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A340	3,405	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B638	669	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
618A000	75	SQYD	Concrete Sidewalk, 4" Thick
618C001	200	SQFT	Detectable Warning Surface
618D000	78	SQYD	Curb Ramp
623A001	20	LF	Concrete Gutter (Valley)
623C003	40	LF	Combination Curb & Gutter, Type C (Modified)
641S500	3	Each	Valve Box Reset
645K500	16	Each	Manhole Frame And Cover Reset
650A000	1,295	CUYD	Topsoil
652A100	14	Acre	Seeding
654A000	11,405	SQYD	Solid Sodding
656A010	16	Acre	Mulching
665J002	1,500	LF	Silt Fence
665O001	1,500	LF	Silt Fence Removal
665Q002	1,250	LF	Wattle
674A000	4,300	LF	Construction Safety Fence
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 68,800.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	3	Mile	Solid Temporary Traffic Stripe
701G253	2,400	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G256	2,650	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701G265	3,880	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	1,826	SQFT	Traffic Control Markings, Class 2, Type A

Item No.	Quantity	Units	Description
703B002	350	SQFT	Traffic Control Legends, Class 2, Type A
703D001	610	SQFT	Temporary Traffic Control Markings
703E001	70	SQFT	Temporary Traffic Control Legends
705A037	232	Each	Pavement Markers, Class A-H, Type 2-D
705A039	35	Each	Pavement Markers, Class A-H, Type 2-A
730H001	600	LF	Loop Wire
740B000	2,224	SQFT	Construction Signs
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone
740O000	1	Each	Pilot Car