

**Alabama Department of Transportation
Proposal Item Summary**

015. STPAA-2822(251)

ETOWAH COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 2.00

for constructing the Resurfacing, Guardrail Installation, and Traffic Stripe on CR-375 (Appalachian Highway) from the junction of SR-74 (US-278) in Hokes Bluff to the junction of SR-25 (US-411). Length 8.007 mi.

The Bracket Estimate on this project is from \$3,441,744 to \$4,206,576.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|---|
| 206D001 | 4,025 | LF | Removing Guardrail |
| 206E008 | 12 | Each | Removing Guardrail End Anchor (All Type) |
| 401B108 | 110,754 | SQYD | Bituminous Treatment G (With Polymer Additive) |
| 405A000 | 8,702 | Gal | Tack Coat |
| 424A361 | 10,675 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B651 | 16,614 | Ton | Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B655 | 500 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B657 | 750 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D |
| 430B043 | 7,050 | Ton | Aggregate Surfacing (1" Down, Crusher Run) |
| 600A000 | 1 | LS | Mobilization |
| 630A001 | 3,813 | LF | Steel Beam Guardrail, Class A, Type 2 |
| 630C022 | 4 | Each | Guardrail End Anchor, Type Special |
| 630C080 | 12 | Each | Guardrail End Anchor, Type 20 Series (MASH) |
| 630G004 | 75 | LF | Steel Beam Guardrail for Culvert, Class A, Type 2, Case 4 |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 184,000.00) |
| 701A231 | 17 | Mile | Solid White, Class 2, Type A Traffic Stripe |
| 701A235 | 7 | Mile | Solid Yellow, Class 2, Type A Traffic Stripe |
| 701A245 | 10 | Mile | Broken Yellow, Class 2, Type A Traffic Stripe |
| 701B205 | 150 | LF | Dotted, Class 2, Type A, Traffic Stripe |
| 701C000 | 19 | Mile | Broken Temporary Traffic Stripe |
| 701C001 | 14 | Mile | Solid Temporary Traffic Stripe |
| 703A004 | 1,807 | SQFT | Traffic Control Markings, Class 2T, Type A |
| 703B004 | 23 | SQFT | Traffic Control Legends, Class 2T, Type A |
| 705A032 | 462 | Each | Pavement Markers, Class A-H, Type 1-B |
| 705A037 | 528 | Each | Pavement Markers, Class A-H, Type 2-D |
| 740B000 | 774 | SQFT | Construction Signs |
| 740E000 | 50 | Each | Cones (36 Inches High) |
| 740M001 | 50 | Each | Ballast For Cone |
| 740O000 | 1 | Each | Pilot Car |