

**Alabama Department of Transportation  
Proposal Item Summary**

**018. STPMN-2620(259)**

**ELMORE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-3 (Ingram Road) from the junction of SR-14 northeast of Millbrook to the junction of CR-7 (Deatsville Highway) in Deatsville. Length 6.443 mi.

The Bracket Estimate on this project is from \$1,531,860 to \$1,872,273.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	340	SQYD	Removing Concrete Driveway
206D003	60	LF	Removing Curb And Gutter
305B071	81	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
405A000	10,808	Gal	Tack Coat
408A052	3,793	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A346	9,638	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	4,037	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 81,000.00)
701A231	13	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	200	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	24	Mile	Solid Temporary Traffic Stripe
701G144	640	LF	Solid White, Class W, Type A Traffic Stripe
701G152	640	LF	Solid Yellow, Class W, Type A Traffic Stripe
701H002	1,280	LF	Solid Traffic Stripe Removed (Tape)
703A002	870	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A
705A032	175	Each	Pavement Markers, Class A-H, Type 1-B
705A037	700	Each	Pavement Markers, Class A-H, Type 2-D
740B000	670	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car