

**Alabama Department of Transportation
Proposal Item Summary**

019. STPMN-5123(250)

MONTGOMERY COUNTY

Contract Time: 40 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-61 (Hobbie Road) from the junction of CR-65 (East Sprague Junction Road)/CR-70 (Hillabee Road) to the junction of SR-9 (US-331) southeast of Hope Hull. Length 9.225 mi.

The Bracket Estimate on this project is from \$1,467,856 to \$1,794,046.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	12,990	Gal	Tack Coat
408A052	2,876	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A346	11,432	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,436	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 78,000.00)
701A231	19	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
701G251	180	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	123	SQFT	Traffic Control Markings, Class 2, Type A
703D001	91	SQFT	Temporary Traffic Control Markings
705A032	268	Each	Pavement Markers, Class A-H, Type 1-B
705A037	914	Each	Pavement Markers, Class A-H, Type 2-D
740B000	704	SQFT	Construction Signs
740O000	1	Each	Pilot Car