

**Alabama Department of Transportation
Proposal Item Summary**

016. NH-0003(644)

MONTGOMERY COUNTY

Contract Time: 50 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-3 (US-31) from the junction of West Boulevard to the Elmore County Line. Length 3.428 mi.

The Bracket Estimate on this project is from \$2,607,501 to \$3,186,946.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210A000	60	CUYD	Unclassified Excavation
401B101	121,950	SQYD	Bituminous Treatment F (With Polymer Additive)
405A000	10,240	Gal	Tack Coat
408A052	144,150	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A280	13,250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424A289	1,170	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B283	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B285	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B287	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
428A001	7	Mile	Scoring Bituminous Pavement Surface
430B043	560	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
654A001	250	SQYD	Solid Sodding (Bermuda)
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 139,800.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	9,140	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	27	Mile	Solid Temporary Traffic Stripe
701G142	4,621	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	4,621	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	4,621	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	4,621	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H001	9,242	LF	Solid Traffic Stripe Removed (Plastic)
701H006	9,242	LF	Broken Traffic Stripe Removed (Plastic)
703A002	2,093	SQFT	Traffic Control Markings, Class 2, Type A
703B002	812	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,586	SQFT	Temporary Traffic Control Markings

Item No.	Quantity	Units	Description
703E001	547	SQFT	Temporary Traffic Control Legends
705A030	800	Each	Pavement Markers, Class A-H, Type 2-C
705A037	60	Each	Pavement Markers, Class A-H, Type 2-D
705A039	16	Each	Pavement Markers, Class A-H, Type 2-A
710A170	50	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	48	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	1,781	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit