

**Alabama Department of Transportation
Proposal Item Summary**

017. NH-0012(577)

MONROE COUNTY

Contract Time: December 31, 2023 Completion Date

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-12 (US-84) from a point 0.367 mile east of the intersection of CR-1 to the junction of Hooks Road southwest of Monroeville. Length 9.552 mi.

The Bracket Estimate on this project is from \$3,126,299 to \$3,821,032.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	50	LF	Removing Guardrail
206E019	4	Each	Removing Guardrail End Anchor (Type 10)
209A001	1	Each	Mailbox Reset, Double
209A002	4	Each	Mailbox Reset, Multiple
212A000	1,009	STA	Machine Grading Shoulders
405A000	13,100	Gal	Tack Coat
408B001	215,555	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	16,824	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	1,337	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	19	Mile	Scoring Bituminous Pavement Surface
430B043	1,000	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	145,700	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	75	LF	Guardrail Reset
650A000	500	CUYD	Topsoil
652A100	12	Acre	Seeding
652C000	70	Acre	Mowing
656A010	12	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 167,989.00)
701A227	21	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,302	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	17	Mile	Broken Temporary Traffic Stripe
701C001	92	Mile	Solid Temporary Traffic Stripe
703A002	15,889	SQFT	Traffic Control Markings, Class 2, Type A
703B002	430	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,110	SQFT	Temporary Traffic Control Markings
703E001	137	SQFT	Temporary Traffic Control Legends
705A030	261	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,362	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,175	Each	Pavement Markers, Class A-H, Type 2-D

Item No.	Quantity	Units	Description
705A038	595	Each	Pavement Markers, Class A-H, Type 2-E
710B021	56	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
711A000	1	LS	Roadway Sign Relocation
740B000	1,183	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car