

**Alabama Department of Transportation  
Proposal Item Summary**

**018. NH-0012(579)**

**CLARKE COUNTY**

Contract Time: December 31, 2023 Completion Date

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-12 (US-84) from the junction of CR-35 to the Monroe County Line. Length 7.811 mi.

The Bracket Estimate on this project is from \$1,648,049 to \$2,014,282.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity | Units | Description   |
|----------|----------|-------|---|
| 209A000  | 1        | Each  | Mailbox Reset, Single   |
| 405A000  | 5,625    | Gal   | Tack Coat   |
| 408B000  | 115,766  | SQYD  | Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)  |
| 410H000  | 1        | Each  | Material Remixing Device  |
| 424A360  | 8,700    | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D            |
| 424A369  | 30       | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D` |
| 424B655  | 100      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D       |
| 424B657  | 100      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D     |
| 430B043  | 100      | Ton   | Aggregate Surfacing (1" Down, Crusher Run)  |
| 433A000  | 112,619  | SQYD  | Scrub Seal  |
| 600A000  | 1        | LS    | Mobilization  |
| 652C000  | 38       | Acre  | Mowing  |
| 698A000  | 1        | LS    | Construction Fuel (Maximum Bid Limited to \$ 88,000.00)   |
| 701A227  | 16       | Mile  | Solid White, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A230  | 9        | Mile  | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A244  | 6        | Mile  | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701B207  | 914      | LF    | Dotted, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701C000  | 18       | Mile  | Broken Temporary Traffic Stripe   |
| 701C001  | 71       | Mile  | Solid Temporary Traffic Stripe  |
| 701G146  | 544      | LF    | Solid White, Class W, Type A Traffic Stripe (5"Wide)  |
| 701G150  | 272      | LF    | Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)   |
| 701G154  | 272      | LF    | Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)  |
| 701G242  | 1,732    | LF    | Broken White, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701H002  | 816      | LF    | Solid Traffic Stripe Removed (Tape)   |
| 701H007  | 272      | LF    | Broken Traffic Stripe Removed (Tape)  |
| 703A002  | 175      | SQFT  | Traffic Control Markings, Class 2, Type A   |
| 703D001  | 525      | SQFT  | Temporary Traffic Control Markings  |
| 705A030  | 187      | Each  | Pavement Markers, Class A-H, Type 2-C   |
| 705A032  | 195      | Each  | Pavement Markers, Class A-H, Type 1-B   |
| 705A037  | 708      | Each  | Pavement Markers, Class A-H, Type 2-D   |
| 740B000  | 1,040    | SQFT  | Construction Signs  |
| 740E000  | 250      | Each  | Cones (36 Inches High)  |
| 740M001  | 250      | Each  | Ballast For Cone  |
| 740O000  | 1        | Each  | Pilot Car   |