

**Alabama Department of Transportation
Proposal Item Summary**

020. NH-0157(530)

LAWRENCE COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-157 from the Morgan County Line to the junction of CR-205 southeast of Moulton. Length 4.849 mi.

The Bracket Estimate on this project is from \$2,944,199 to \$3,598,466.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
405A000	23,699 Gal	Tack Coat
408B001	236,988 SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1 Each	Material Remixing Device
424A340	2,286 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A360	15,087 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	2,180 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,000 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,000 Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	20 Mile	Scoring Bituminous Pavement Surface
430B042	1,518 Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1 LS	Mobilization
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 172,000.00)
701A227	11 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	10,960 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20 Mile	Broken Temporary Traffic Stripe
701C001	22 Mile	Solid Temporary Traffic Stripe
703A002	3,184 SQFT	Traffic Control Markings, Class 2, Type A
703B002	830 SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,248 SQFT	Temporary Traffic Control Markings
705A030	680 Each	Pavement Markers, Class A-H, Type 2-C
740B000	1,799 SQFT	Construction Signs
740D000	100 Each	Channelizing Drums
740E000	300 Each	Cones (36 Inches High)
740M001	300 Each	Ballast For Cone
741C010	2 Each	Portable Sequential Arrow And Chevron Sign Unit