

**Alabama Department of Transportation
Proposal Item Summary**

021. NH-0215(506)

TUSCALOOSA COUNTY

Contract Time: 70 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-215 (Veterans Memorial Parkway) from the junction of 10th Avenue East to the junction of the Traditions Condominiums Entrance in Tuscaloosa. Length 1.719 mi.

The Bracket Estimate on this project is from \$2,166,896 to \$2,648,429.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	15,186	Gal	Tack Coat
408A053	75,928	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,080	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	426	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	6,656	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	558	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B684	764	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 115,000.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,546	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	14	Mile	Broken Temporary Traffic Stripe
701C001	17	Mile	Solid Temporary Traffic Stripe
701F000	11,092	LF	Dotted Temporary Traffic Stripe
701H001	17	LF	Solid Traffic Stripe Removed (Plastic)
703A002	2,738	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,099	SQFT	Traffic Control Legends, Class 2, Type A
703C001	115	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D002	5,476	SQFT	Temporary Traffic Control Markings (Paint)
703E002	2,197	SQFT	Temporary Traffic Control Legends (Paint)
705A030	615	Each	Pavement Markers, Class A-H, Type 2-C
728A000	2	Each	Truck Mounted Impact Attenuator Unit
730A012	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-215 (Veterans Memorial Parkway) at Eastwood Avenue (10th Avenue))
730A013	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-215 (Veterans Memorial Parkway) at University Mall)
730A014	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-215 (Veterans Memorial Parkway) at 13th Avenue)
730A015	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-215 (Veterans Memorial Parkway) at Kicker Road)
730A017	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-215 (Veterans Memorial Parkway) at 26th Avenue)

Item No.	Quantity	Units	Description
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-215 (Veterans Memorial Parkway) at Eastwood Avenue (10th Avenue))
730C001	1	LS	Furnishing And Installing Traffic Control Unit (SR-215 (Veterans Memorial Parkway) at University Mall)
730C002	1	LS	Furnishing And Installing Traffic Control Unit (SR-215 (Veterans Memorial Parkway) at 13th Avenue)
730C003	1	LS	Furnishing And Installing Traffic Control Unit (SR-215 (Veterans Memorial Parkway) at Kicker Road)
730C004	1	LS	Furnishing And Installing Traffic Control Unit (SR-215 (Veterans Memorial Parkway) at 26th Avenue)
730H001	1,000	LF	Loop Wire
730U015	1	LS	Video Detection System (SR-215 (Veterans Memorial Parkway) at University Mall)
730U016	1	LS	Video Detection System (SR-215 (Veterans Memorial Parkway) at 13th Avenue)
730U017	1	LS	Video Detection System (SR-215 (Veterans Memorial Parkway) at Kicker Road)
730U018	1	LS	Video Detection System (SR-215 (Veterans Memorial Parkway) at 26th Avenue)
730U450	1	LS	Magnetometer Detection System (SR-215 (Veterans Memorial Parkway) at Eastwood Avenue (10th Avenue))
730U451	1	LS	Magnetometer Detection System (SR-215 (Veterans Memorial Parkway) at University Mall)
730U452	1	LS	Magnetometer Detection System (SR-215 (Veterans Memorial Parkway) at 13th Avenue)
730U453	1	LS	Magnetometer Detection System (SR-215 (Veterans Memorial Parkway) at Kicker Road)
730U454	1	LS	Magnetometer Detection System (SR-215 (Veterans Memorial Parkway) at 26th Avenue)
740B000	1,434	SQFT	Construction Signs
740C000	12	SQFT	Special Construction Signs
740D000	250	Each	Channelizing Drums
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
745A000	96	HOUR	Uniformed Police Officer