

**Alabama Department of Transportation
Proposal Item Summary**

024. NH-HSIP-0016(532)

MOBILE COUNTY

Contract Time: December 31, 2023 Completion Date

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, Traffic Signal Updates, and Traffic Stripe on SR-16 (US-90) from the intersection of SR-163 to the intersection of US-98 (Broad Street) in Mobile. Length 1.936 mi.

The Bracket Estimate on this project is from \$1,167,848 to \$1,427,370.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	116	SQYD	Removing Concrete Sidewalk
206D003	28	LF	Removing Curb And Gutter
405A000	6,916	Gal	Tack Coat
408A052	69,159	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A360	5,706	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618A000	28	SQYD	Concrete Sidewalk, 4" Thick
618C001	94	SQFT	Detectable Warning Surface
618D000	84	SQYD	Curb Ramp
623C000	16	LF	Combination Curb & Gutter, Type C
654A001	41	SQYD	Solid Sodding (Bermuda)
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 62,000.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,041	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	21	Mile	Broken Temporary Traffic Stripe
701C001	24	Mile	Solid Temporary Traffic Stripe
703A002	5,945	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,132	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,792	SQFT	Temporary Traffic Control Markings
703E001	752	SQFT	Temporary Traffic Control Legends
705A030	309	Each	Pavement Markers, Class A-H, Type 2-C
705A032	14	Each	Pavement Markers, Class A-H, Type 1-B
705A037	564	Each	Pavement Markers, Class A-H, Type 2-D
705A038	27	Each	Pavement Markers, Class A-H, Type 2-E
730H001	32,168	LF	Loop Wire
730Q020	68	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 3 Section
730Q022	4	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 5 Section
740B000	1,116	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums

Item No.	Quantity	Units	Description
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit