

**Alabama Department of Transportation
Proposal Item Summary**

025. NH-HSIP-0042(542)

MOBILE COUNTY

Contract Time: December 31, 2023 Completion Date

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, Traffic Signal Upgrades, and Traffic Stripe on SR-42 (US-98) from the intersection of South Broad Street to the junction of South Royal Street/Bankhead Tunnel (MP 27.433) in Mobile. Length 0.780 mi.

The Bracket Estimate on this project is from \$739,349 to \$903,649.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	3,480	Gal	Tack Coat
408A052	34,614	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	2,871	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
614A000	5	CUYD	Slope Paving
618A000	1	SQYD	Concrete Sidewalk, 4" Thick
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,965.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,101	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
703A002	9,508	SQFT	Traffic Control Markings, Class 2, Type A
703B002	314	SQFT	Traffic Control Legends, Class 2, Type A
703D001	6,548	SQFT	Temporary Traffic Control Markings
703H000	1,770	SQFT	Specialty Traffic Control Markings
705A030	374	Each	Pavement Markers, Class A-H, Type 2-C
705A032	191	Each	Pavement Markers, Class A-H, Type 1-B
705A037	201	Each	Pavement Markers, Class A-H, Type 2-D
705A038	103	Each	Pavement Markers, Class A-H, Type 2-E
707H001	172	LF	Raised Curb Channelizer, White
730H001	18,092	LF	Loop Wire
730Q020	52	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 3 Section
730Q021	1	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 4 Section
740B000	992	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit