

**Alabama Department of Transportation
Proposal Item Summary**

031. RP-NH-0133(511)

COLBERT COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 7.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-133 from the intersection of Avalon Avenue in Muscle Shoals to a point 0.660 mile south of the intersection of Reservation Road. Length 2.158 mi.

The Bracket Estimate on this project is from \$1,968,021 to \$2,405,359.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	2	Each	Removing Guardrail End Anchor (All Type)
405A000	21,644	Gal	Tack Coat
408B001	216,436	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A280	9,410	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B285	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B287	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
428A001	1	Mile	Scoring Bituminous Pavement Surface
430B042	338	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 117,000.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,077	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	13	Mile	Solid Temporary Traffic Stripe
703A002	13,403	SQFT	Traffic Control Markings, Class 2, Type A
703B002	627	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,684	SQFT	Temporary Traffic Control Markings
705A030	1,193	Each	Pavement Markers, Class A-H, Type 2-C
705A037	535	Each	Pavement Markers, Class A-H, Type 2-D
730H001	8,100	LF	Loop Wire
730I001	2,100	LF	Loop Detector Lead-In-Cable
730K000	2	Each	Traffic Signal Junction Box
730L005	2,100	LF	2", Non-Metallic, Conduit
740B000	1,073	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit