

**Alabama Department of Transportation
Proposal Item Summary**

037. STPNU-0087(517)

PIKE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-87 from the Coffee County Line to the junction of SR-167 south of Troy. Length 4.322 mi.

The Bracket Estimate on this project is from \$1,461,743 to \$1,786,575.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	456	STA	Machine Grading Shoulders
405A000	7,578	Gal	Tack Coat
408A052	72,175	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	7,940	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	50	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	1,690	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	38	Acre	Mowing
656A010	5	Acre	Mulching
665A000	13	Acre	Temporary Seeding
665B001	38	Ton	Temporary Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
666A001	5	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 78,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	14	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	282	SQFT	Traffic Control Markings, Class 2, Type A
703D001	282	SQFT	Temporary Traffic Control Markings
705A032	96	Each	Pavement Markers, Class A-H, Type 1-B
705A037	382	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,034	SQFT	Construction Signs

Item No.	Quantity	Units	Description
740C000	23	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car