

**Alabama Department of Transportation  
Proposal Item Summary**

**038. STPNU-0187(518)**

**FRANKLIN COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-187 from the junction of CR-22 to the intersection of SR-24 northeast of Hodges. Length 5.681 mi.

The Bracket Estimate on this project is from \$1,405,844 to \$1,718,253.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	9,652	Gal	Tack Coat
408B001	97,039	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	7,867	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	95	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	11	Mile	Scoring Bituminous Pavement Surface
430B042	875	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,400.00)
701A227	12	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	41	Mile	Solid Temporary Traffic Stripe
701G146	432	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	432	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	464	SQFT	Traffic Control Markings, Class 2, Type A
703B002	273	SQFT	Traffic Control Legends, Class 2, Type A
703D001	928	SQFT	Temporary Traffic Control Markings
705A032	111	Each	Pavement Markers, Class A-H, Type 1-B
705A037	636	Each	Pavement Markers, Class A-H, Type 2-D
740B000	921	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car