

**Alabama Department of Transportation  
Proposal Item Summary**

**039. STPUC-0248(502)**

**DALE AND COFFEE COUNTIES**

Contract Time: 35 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-248 from the junction of Freedom Drive in Enterprise to a point near the Fort Rucker Gate (MP 6.066). Length 2.687 mi.

The Bracket Estimate on this project is from \$1,499,890 to \$1,833,199.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
210A000	287	CUYD	Unclassified Excavation
212A000	50	STA	Machine Grading Shoulders
405A000	7,974	Gal	Tack Coat
408A052	79,452	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	7,482	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	343	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
430B043	31	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
614A000	46	CUYD	Slope Paving
623B000	385	LF	Concrete Curb, Type N
623B001	200	LF	Concrete Curb, Type N Special
650A000	30	CUYD	Topsoil
652A100	7	Acre	Seeding
652C000	7	Acre	Mowing
654A001	506	SQYD	Solid Sodding (Bermuda)
656A010	7	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 79,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,000	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	18	Mile	Broken Temporary Traffic Stripe
701C001	45	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	2,595	SQFT	Traffic Control Markings, Class 2, Type A
703B002	180	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,767	SQFT	Temporary Traffic Control Markings
705A030	404	Each	Pavement Markers, Class A-H, Type 2-C
705A032	786	Each	Pavement Markers, Class A-H, Type 1-B
705A037	367	Each	Pavement Markers, Class A-H, Type 2-D

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740B000	1,274	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740D000	250	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit