

**Alabama Department of Transportation
Proposal Item Summary**

042. STPAA-HSIP-0021(579)

ESCAMBIA COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 2.00

for constructing the Resurfacing, Bridge Guardrail Retrofit, Guardrail Replacement, and Traffic Stripe on SR-21 from 0.500 mile north of the I-65 Overpass (MP 8.533) to the south end of the Little River Bridge (MP 18.658) at the Monroe County Line. Length 10.124 mi.

The Bracket Estimate on this project is from \$1,835,236 to \$2,243,066.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	20	Each	Removing Guardrail End Anchor (All Type)
405A000	17,187	Gal	Tack Coat
410H000	1	Each	Material Remixing Device
424A360	11,354	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	21	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
629D002	2	Each	Bridge Guardrail Retrofit, Type BC
629D003	4	Each	Bridge Guardrail Retrofit, Type SC
630C079	6	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	14	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	784	LF	Guardrail Reset
650A000	7,981	CUYD	Topsoil
652A100	15	Acre	Seeding
652C000	78	Acre	Mowing
654A001	639	SQYD	Solid Sodding (Bermuda)
656A010	15	Acre	Mulching
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	15	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 98,000.00)
701A227	21	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	14	Mile	Broken Temporary Traffic Stripe
701C001	59	Mile	Solid Temporary Traffic Stripe
701G146	680	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	340	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	680	LF	Solid Traffic Stripe Removed (Tape)
701H007	340	LF	Broken Traffic Stripe Removed (Tape)
703A002	820	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	280	SQFT	Temporary Traffic Control Markings
703E001	96	SQFT	Temporary Traffic Control Legends
705A032	141	Each	Pavement Markers, Class A-H, Type 1-B
705A037	804	Each	Pavement Markers, Class A-H, Type 2-D
710A170	18	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B001	28	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
740B000	744	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car