

**Alabama Department of Transportation
Proposal Item Summary**

043. STPNU-HSIP-0129(507)

MARION COUNTY

Contract Time: 50 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-129 from 0.470 mile west of the junction of Lauderdale Road to the Winston County Line. Length 4.053 miles

The Bracket Estimate on this project is from \$2,421,613 to \$2,959,749.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	100	SQYD	Removing Concrete Driveway
209A000	21	Each	Mailbox Reset, Single
209A002	1	Each	Mailbox Reset, Multiple
305B077	2,963	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	19,040	Gal	Tack Coat
408B001	61,434	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	3,890	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	239	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	4,944	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B662	13	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	3,904	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	1,581	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
433A000	59,445	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 130,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	77	Mile	Solid Temporary Traffic Stripe
703A002	1,346	SQFT	Traffic Control Markings, Class 2, Type A
703D001	4,260	SQFT	Temporary Traffic Control Markings
705A032	169	Each	Pavement Markers, Class A-H, Type 1-B
705A037	165	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,431	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	