

**Alabama Department of Transportation
Proposal Item Summary**

044. STPNU-HSIP-0148(504)

CLAY COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Resurfacing (Micro-Surfacing Seal Coat and Scrub Seal), Bridge Guardrail Retrofit, Guardrail Installation, and Traffic Stripe on SR-148 from the Talladega County Line to the junction of SR-9 southwest of Ashland. Length 15.297 mi.

The Bracket Estimate on this project is from \$2,646,977 to \$3,235,194.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	472	LF	Removing Guardrail
206E008	12	Each	Removing Guardrail End Anchor (All Type)
209A000	3	Each	Mailbox Reset, Single
403B001	3,283	Ton	Micro-Surfacing Seal Coat, Type III
405A000	2,500	Gal	Tack Coat
424B639	350	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	350	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	6,565	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	31	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	124,925	SQYD	Scrub Seal
600A000	1	LS	Mobilization
610D003	3,470	SQYD	Filter Blanket, Geotextile
629D003	4	Each	Bridge Guardrail Retrofit, Type SC
630A001	350	LF	Steel Beam Guardrail, Class A, Type 2
630A004	222	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
665A000	15	Acre	Temporary Seeding
665B001	45	Ton	Temporary Mulching
665G000	200	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	5,200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 150,000.00)
701A227	31	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	13	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	18	Mile	Broken Temporary Traffic Stripe
701C001	55	Mile	Solid Temporary Traffic Stripe
701C006	1	Mile	Solid Temporary Traffic Stripe (Removable Tape)
701G146	771	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	386	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	771	LF	Solid Traffic Stripe Removed (Tape)
701H007	386	LF	Broken Traffic Stripe Removed (Tape)

Item No.	Quantity	Units	Description
703A002	460	SQFT	Traffic Control Markings, Class 2, Type A
703D001	42	SQFT	Temporary Traffic Control Markings
705A032	780	Each	Pavement Markers, Class A-H, Type 1-B
705A037	800	Each	Pavement Markers, Class A-H, Type 2-D
740B000	995	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740O000	1	Each	Pilot Car