

**Alabama Department of Transportation  
Proposal Item Summary**

**050. STPNU-0006(596)**

**BULLOCK COUNTY**

Contract Time: 65 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-6 (US-82) from the Montgomery County Line to a point east of the Bowlin Creek Bridge (MP 193.683). Length 14.342 mi.

The Bracket Estimate on this project is from \$3,176,966 to \$3,882,958.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	16,255	Gal	Tack Coat
408A052	238,211	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	19,635	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	12	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	2,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	28	Mile	Scoring Bituminous Pavement Surface
430B043	1,865	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665G000	100	Each	Sand Bags
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 171,443.00)
701A227	29	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	19	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20	Mile	Broken Temporary Traffic Stripe
701C001	96	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	2,179	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	749	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	885	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	8,084	SQFT	Traffic Control Markings, Class 2, Type A
703D001	944	SQFT	Temporary Traffic Control Markings
705A032	332	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,198	Each	Pavement Markers, Class A-H, Type 2-D
705A039	192	Each	Pavement Markers, Class A-H, Type 2-A
740B000	1,362	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car