

**Alabama Department of Transportation
Proposal Item Summary**

051. STPNU-0009(587)

CLEBURNE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-9 from a point on the I-20 Overpass (MP 213.475) to the junction of SR-4 (US-78) in Heflin. Length 1.598 mi.

The Bracket Estimate on this project is from \$1,063,998 to \$1,300,443.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	563	LF	Removing Guardrail
206E008	2	Each	Removing Guardrail End Anchor (All Type)
401B108	60,376	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	6,038	Gal	Tack Coat
408B001	60,376	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,282	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A001	563	LF	Steel Beam Guardrail, Class A, Type 2
630C077	1	Each	Guardrail End Anchor, Type 8 (MASH)
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 56,000.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	3	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B027	248	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B207	830	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	20	Mile	Solid Temporary Traffic Stripe
701E003	2,976	LF	Solid Temporary Traffic Stripe (Tape)
701E013	744	LF	Broken Temporary Traffic Stripe (Tape)
701G146	496	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	496	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	6,762	SQFT	Traffic Control Markings, Class 2, Type A
703B002	359	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,000	SQFT	Temporary Traffic Control Markings
705A030	400	Each	Pavement Markers, Class A-H, Type 2-C
705A037	300	Each	Pavement Markers, Class A-H, Type 2-D
705A038	34	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,066	SQFT	Construction Signs
740D000	300	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)

Item No.	Quantity	Units	Description
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit