

**Alabama Department of Transportation
Proposal Item Summary**

053. STPNU-HSIP-0007(555)

GREENE COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-7 (US-11) from the intersection of CR-20 in Boligee to a point south of Greene County High School (MP 41.032) southwest of Eutaw. Length 6.951 mi.

The Bracket Estimate on this project is from \$3,643,908 to \$4,453,665.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	2,375	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
206E014	4	Each	Removing Guardrail End Anchor (Type 2A)
210D021	520	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
305B077	1,300	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401B108	112,414	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	21,583	Gal	Tack Coat
408A052	115,372	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A340	12,532	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	159	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	4,283	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	9,526	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	21	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
629D002	4	Each	Bridge Guardrail Retrofit, Type BC
630A001	888	LF	Steel Beam Guardrail, Class A, Type 2
630A034	1,438	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	42	CUYD	Topsoil
654A001	749	SQYD	Solid Sodding (Bermuda)
665Q002	700	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 193,077.00)
701A227	14	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	33	Mile	Broken Temporary Traffic Stripe
701C001	78	Mile	Solid Temporary Traffic Stripe
701G146	1,153	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	168	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	985	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	2,138	LF	Solid Traffic Stripe Removed (Tape)
701H007	168	LF	Broken Traffic Stripe Removed (Tape)
703A002	807	SQFT	Traffic Control Markings, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	622	SQFT	Temporary Traffic Control Markings
705A032	172	Each	Pavement Markers, Class A-H, Type 1-B
705A037	324	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,796	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740O000	1	Each	Pilot Car