

**Alabama Department of Transportation
Proposal Item Summary**

055. STPNU-HSIP-0053(596) & STPAA-0053(599)

HOUSTON COUNTY

Contract Time: 120 Working Days

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-53 from the Florida State Line to the intersection of SR-210 (Ross Circle) in Dothan. Length 18.607 mi.

The Bracket Estimate on this project is from \$4,786,515 to \$5,850,185.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	688	LF	Removing Guardrail
206E008	24	Each	Removing Guardrail End Anchor (All Type)
209A000	2	Each	Mailbox Reset, Single
212A000	721	STA	Machine Grading Shoulders
405A000	41,854	Gal	Tack Coat
408B001	347,336	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A341	9,613	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	348	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A361	18,786	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	144	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	2,804	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B654	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B700	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	34	Mile	Scoring Bituminous Pavement Surface
430B043	275	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	101	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	20	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G001	300	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 1
650A000	3,560	CUYD	Topsoil
652A100	7	Acre	Seeding
652C000	122	Acre	Mowing
656A010	7	Acre	Mulching
659C002	1,100	SQYD	Erosion Control Product, Type S2
665A000	20	Acre	Temporary Seeding
665B001	60	Ton	Temporary Mulching
665E000	300	SQYD	Polyethylene
665G000	200	Each	Sand Bags

Item No.	Quantity	Units	Description
665J002	650	LF	Silt Fence
665O001	650	LF	Silt Fence Removal
665Q002	650	LF	Wattle
666A001	7	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 259,700.00)
701A227	39	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	23	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,445	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	32	Mile	Broken Temporary Traffic Stripe
701C001	118	Mile	Solid Temporary Traffic Stripe
701D007	2	Mile	Solid Traffic Stripe Removed (Paint)
701D008	2	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	2	Mile	Broken Traffic Stripe Removed (Paint)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	1,000	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	500	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	11,061	SQFT	Traffic Control Markings, Class 2, Type A
703B002	699	SQFT	Traffic Control Legends, Class 2, Type A
703D001	8,313	SQFT	Temporary Traffic Control Markings
703E001	546	SQFT	Temporary Traffic Control Legends
703H000	5	SQFT	Specialty Traffic Control Markings
705A030	250	Each	Pavement Markers, Class A-H, Type 2-C
705A032	821	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,942	Each	Pavement Markers, Class A-H, Type 2-D
740B000	4,137	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740D000	75	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car