

**Alabama Department of Transportation
Proposal Item Summary**

066. ATRP2-66-2021-066

WILCOX COUNTY

Contract Time: 40 Working Days

for constructing the Intersection Improvements (Drainage Improvements; Sidewalk and Crosswalk Installation) on SR-10 at CR-22 in Camden. Length 0.556 mi.

The Bracket Estimate on this project is from \$459,385 to \$561,470.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206C000	549	SQYD	Removing Concrete Sidewalk
206C002	20	SQYD	Removing Concrete Slope Paving
206D000	51	LF	Removing Pipe
206D002	12	LF	Removing Curb
210A000	830	CUYD	Unclassified Excavation
210D021	477	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	168	CUYD	Structure Excavation
214B001	69	CUYD	Foundation Backfill, Commercial
424A341	5	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	9	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
530B009	56	LF	88" Span, 54" Rise Roadway Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610C001	100	Ton	Loose Riprap, Class 2
610D003	50	SQYD	Filter Blanket, Geotextile
618A000	1,071	SQYD	Concrete Sidewalk, 4" Thick
618B002	183	SQYD	Concrete Driveway, 6" Thick
618C001	110	SQFT	Detectable Warning Surface
618D000	33	SQYD	Curb Ramp
634A002	305	LF	Industrial Fence, 6 Feet High
650A000	351	CUYD	Topsoil
654A001	1,577	SQYD	Solid Sodding (Bermuda)
665E000	2,000	SQYD	Polyethylene
665F000	200	Each	Hay Bales
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,574.00)
703A002	371	SQFT	Traffic Control Markings, Class 2, Type A
710A160	54	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	112	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
711A000	1	LS	Roadway Sign Relocation
730Y620	1	LS	Furnishing And Installing Pedestal Pole And Foundation With Pedestrian Signal Features .
730Y621	1	LS	Furnishing And Installing Pedestal Pole And Foundation With Pedestrian Signal Features .
740B000	561	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)

Item No.	Quantity	Units	Description
740F002	8	Each	Barricades, Type III
740M001	200	Each	Ballast For Cone
742A001	4	Each	Portable Changeable Message Sign, Type 2