

**Alabama Department of Transportation
Proposal Item Summary**

007. IM-I020(368) & IM-I020(369)

CLEBURNE COUNTY

Contract Time: 175 Working Days

DBE Goal Percent: 3.00

for constructing the Clearing, Micro-Milling, Resurfacing (Open Graded Friction Course), and Traffic Stripe on I-20 from the SR-46 Overpass in Heflin to the Georgia State Line. Length 13.763 mi.

The Bracket Estimate on this project is from \$4,562,964 to \$5,576,956.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201C000	1	LS	Clearing
206D003	399	LF	Removing Curb And Gutter
305A057	50	CUYD	Crushed Aggregate, Section 825,
405A000	100	Gal	Tack Coat
408B000	172,603	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	11,016	Ton	Polymer Modified Open Graded Friction Course
420B000	18,987	Gal	Open Graded Friction Course Tack Coat
424A280	80	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B285	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B287	106	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
430B043	25	Ton	Aggregate Surfacing (1" Down, Crusher Run)
432A000	182,070	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
610D003	7,500	SQYD	Filter Blanket, Geotextile
614A000	2	CUYD	Slope Paving
623C000	269	LF	Combination Curb & Gutter, Type C
650A000	54	CUYD	Topsoil
654A000	80	SQYD	Solid Sodding
665A000	126	Acre	Temporary Seeding
665B001	378	Ton	Temporary Mulching
665G000	250	Each	Sand Bags
665J002	100,000	LF	Silt Fence
665L000	750	LF	Floating Basin Boom
665O001	100,000	LF	Silt Fence Removal
665P005	12	Each	Inlet Protection, Stage 3 Or 4
665Q002	6,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 266,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	16	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,200	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	31	Mile	Broken Temporary Traffic Stripe
701C001	35	Mile	Solid Temporary Traffic Stripe
703A002	5,705	SQFT	Traffic Control Markings, Class 2, Type A
703B002	105	SQFT	Traffic Control Legends, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	105	SQFT	Temporary Traffic Control Markings
705A030	2,174	Each	Pavement Markers, Class A-H, Type 2-C
705A031	50	Each	Pavement Markers, Class A-H, Type 1-A
705A032	650	Each	Pavement Markers, Class A-H, Type 1-B
740B000	3,248	SQFT	Construction Signs
740D000	600	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A003	4	Each	Portable Changeable Message Sign, Type 3