

**Alabama Department of Transportation
Proposal Item Summary**

015. STPAA-0003(651)

BUTLER COUNTY

Contract Time: 30 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-3 (US-31) from the Conecuh County Line to the junction of SR-55 in McKenzie. Length 1.549 mi.

The Bracket Estimate on this project is from \$923,440 to \$1,128,649.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	20	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
305B077	30	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	6,873	Gal	Tack Coat
408A051	126	SQYD	Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
408A053	22,784	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	1,253	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	25	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	2,506	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	2,194	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	3	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	600	CUYD	Topsoil
652A100	2	Acre	Seeding
652C000	10	Acre	Mowing
656A010	2	Acre	Mulching
665A000	2	Acre	Temporary Seeding
665B001	4	Ton	Temporary Mulching
665J002	420	LF	Silt Fence
665O001	420	LF	Silt Fence Removal
665Q002	420	LF	Wattle
666A001	2	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 49,130.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C001	23	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	40	SQFT	Traffic Control Markings, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	120	SQFT	Temporary Traffic Control Markings
705A037	97	Each	Pavement Markers, Class A-H, Type 2-D
740B000	632	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	1	Each	Portable Changeable Message Sign, Type 2